




# ALBA, Status and Operation

Francis Perez





**Introduction to ALBA**  
**Status**  
**Operation**




# Introduction to ALBA

The ALBA Team  
We are today ~150



## and I got new responsibilities!




The screenshot shows the ALBA website's news section. The header includes the ALBA logo, a search bar, and navigation tabs for 'about', 'divisions', 'beamlines', 'news', 'events', 'jobs', 'phone book', 'intranet', and 'user office'. The breadcrumb trail reads 'you are here: home → news & events → all news → new division heads'. The main content area is titled 'New Division Heads' and includes a sub-header 'Appointment of the new Heads of ALBA Accelerator Division and Experimental Division'. The text below states: 'I am pleased to announce the appointment of the new Heads of ALBA Accelerator Division and Experimental Division.' To the right of the text is a small image of a large circular building. A navigation sidebar on the left lists 'All events', 'All news', and 'New Division Heads'. A text box on the left side of the page contains the text 'Responsibilities associated with ties!!' with a line pointing to a photo of Dr. Francis Pérez.

**New Division Heads**  
Created by [Anne-Cécile KLORA](#) — last modified Sep 04, 2012 09:47 AM


**Appointment of the new Heads of ALBA Accelerator Division and Experimental Division**

I am pleased to announce the appointment of the new Heads of ALBA Accelerator Division and Experimental Division.



Dr. Francis Pérez, who is one of the ALBA founders, is already acting as Head of the Accelerator Division since August. He has participated to the ALBA project since its beginning, with an active role in the design, construction, commissioning and operation of the accelerator. He has always been one of the major collaborators of the former Accelerator Division Head, Dieter Einfeld, to whom go our congratulations for his realization and our best wishes for his future.

*Responsibilities associated with ties!!*



- ✓ 3 GeV electron Storage Ring
- ✓ 31 beamlines (7 on day one)
- ✓ Funding is 50% Spanish – 50% Catalan Governments
- ✓ Designed for sub-micron stability and top-up operation






# ALBA History

ALBA founded	April 2003
ALBA 1st worker	Dec 2003
Design work	2004-2005
Start main building works	July 2006
Start Linac installation	Feb 2008
Linac commissioning	Sept - Oct 2008
Booster and SR installation	Feb – Dec 2009
Booster commissioning	Jan – Oct 2010
SR Installation	Feb – Dec 2010
Storage Ring commissioning	March – Nov 2011
Beamlines commissioning	Oct 2011 – Dec 2012
<b>Start of Users Operation</b>	<b>May 2012</b>








Bending

RF cavities

In vacuum undulator



SR

Booster

Electron beam energy	3.0 GeV
Storage Ring Circumference	268.8 m
Number of cells	16
Symmetry	4
<hr/>	
Straight section lengths	4 x 8.0 m (3 ID's+Inj)
	12 x 4.4 m (12 ID's)
	8 x 2.6 m (2 ID's+RF+Diagn)
<hr/>	
Beam current	400 mA
Emittance	4 nm.rad
Lifetime	> 10 h



# ALBA BEAMLINES

## Phase 1:

*7 Beamlines* under commissioning

6 ID's and 1 bending magnet port

In addition, *2 bending magnet* ports for Electron Beam Diagnostic

## Phase 2:


8 proposal have been evaluated

*2* new beamlines are approved but pending financial budget

## In total:

Capability for *17 ID* beamlines

And *14 bending magnet* beamlines






# Status


## Main linac parameters:

Parameters		Specifications	Working
E	MeV	100-130	110
$\Delta E/E$	rms	< 0.50	0.16
Norm. $\epsilon_{x,y}$	mm·mrad	< 30	< 15


- All parameters within specs
- Operation modes: single bunch & multibunch




$\Delta E/E = 0.16\%$  (rms)



$\epsilon_x$  (norm.)  $\approx 9 \text{ mm}\cdot\text{mrad}$






Few bunches mode  
0.25 nC/bunch at linac exit



Multibunch mode  
4 nC at linac exit

## Main BO parameters:

- C = 249.6 m, shares tunnel with SR
- E = 110 MeV to 3.0 GeV
- $\epsilon_x \approx 10 \text{ nm}\cdot\text{mrad}$
- Repetition rate:     1 Hz for comm.  
                              3.125 Hz for operation
- Good agreement with the model






	Nominal	Achieved
Energy	3 GeV	3 GeV
Max. Current	400 mA	200 mA
Tunes	18.18, 8.37	18.15, 8.37
Emittance	4.3 nm·rad	4.4 ± 0.4 nm·rad
Energy spread	1.05·10 <sup>-3</sup>	1.00·10 <sup>-3</sup>
Coupling	< 1 %	0.5 %
Lifetime @ 100 mA	>10 h	10 h
Ah accumulated		>100

Phase I beamlines:

6 x IDs

All IDs fully operational



1 x Bending



❑ Spectral range: from UV (80 eV) to hard x-rays (50 keV)

❑ High brilliance: 10<sup>20</sup> at 2 keV

## Raw orbit without correctors after BBA



RMS Error: Horizontal 1.157523 mm Vertical 0.821631 mm  
 Mean Error: Horizontal -0.182247 mm Vertical 0.175041 mm

03-Jun-2011 08:56:36

*BBA: Beam based alignment.*  
 → align BPM to center of quad


Horizontal orbit < 3mm

Vertical orbit < 2 mm



**Good alignment**

## Beam Stability over 24 h



RMS-Values:

$$\sigma_x = 0.5 \mu\text{m}$$


$$\sigma_y = 0.2 \mu\text{m}$$

SOFB (Slow Orbit FeedBack)


- Running every 3 s
- With RF frequency included on SOFB

Long term drift @ MSPD

Vertical plane



# “BUILDING” STABILITY






# Operation

# End 2011: Transition to Operation

2011		October 2011				November 2011				December 2011				
Shift	7-15	15-22	Day	Week	Shift	7-15	15-22	Day	Week	Shift	7-15	15-22	Day	Week
								1						
								2						
								3					1	BL BL
								4					2	BL BL
			1	40				5					3	
			2					6					4	
			3					7	45				5	49
			4					8					6	
			5					9					7	
			6					10					8	
			7					11					9	
			8					12					10	
			9					13					11	
			10	41				14	46				12	
			11					15					13	
			12					16					14	
			13					17					15	
			14					18					16	
			15					19					17	
			16					20					18	
			17	42				21	47				19	51
			18					22					20	
			19					23					21	
			20					24					22	
			21					25					23	
			22					26					24	
			23					27					25	
			24	43				28	48				26	52
			25					29					27	
			26					30					28	
			27										29	
			28										30	
			29										31	
			30											
			31	44										







you are here: [home](#) → [news & events](#) → [all news](#) → [the first users have started their experiments at alba](#)

navigation

- All events
- All news
- The first users have started their experiments at ALBA**

## The first users have started their experiments at ALBA


Created by [Anne-Cécile KLORA](#) — last modified May 17, 2012 12:52 PM

**BOREAS is the first of ALBA 7 beamlines to be available to users.**

The standard proposal 'Ferrite magnetic nanoparticles and hybrid superconducting layers: a XMCD spectroscopic study', granted with 18 shifts, started running experiments at ALBA on May 7th, 2012.

The aim of the experiment is to clarify and characterize the atomic origin of the magnetism in different ferrite nanoparticles, both in assynthesized form as well as embedded in high temperature superconductor (HTS) thin films.

Alba would like to thank all participants in this call for proposals for their interest in our Facility and the high level of scientific proposals, as acknowledged by the Scientific Panel.

ALBA acting Director, the User Office team, the BOREAS beamline team and the first external users from Unidad de Química Inorgánica- Departamento de Química- UAB, Barcelona.

## Statistics Jan-Sept 2012

### ☐ Beamline operation:


☐ 2073 planned

☐ 1950 delivered





☐ 94 % beam availability:


Hours for BLs: Planed vs. Delivered



Hours for BLs: % Delivered vs Planned







- ❑ **Main specifications for ALBA have been reached**
  
- ❑ **ALBA is already open to users**
  - ❑ **2013 will have:**
    - ❑ **3600 hours for BLs (2800 for users)**
    - ❑ **1400 hours for Accelerators**
  
- ❑ **Future work:**
  - ❑ **FOFB**
  - ❑ **Top-up**
  - ❑ **Fast Feedback system**
  - ❑ **Increase operation current**



**Thank you**