

IMMW17-2011: Project ALBA

Contents
1.) General Information
2.) Linac
3.) Booster Synchrotron
4.) Storage Ring

Dieter Einfeld, CELLS-ALBA

IMMW17-2011, 21th September 2011

Accelerator

Division



IMMW17-2011: Project ALBA

Contents
1.) General Information
2.) Linac
3.) Booster Synchrotron
4.) Storage Ring

Dieter Einfeld, CELLS-ALBA

1

IMMW17-2011, 21th September 2011

Accelerator

Division



History of the Project

Accelerator Division

- 1992-4: First plans for a light source in Spain.
- 1997: Finishing the conceptual design report
- 2003: Approval of the project by the Spanish- and the Catalonian Government. Site selected in the Valles area, close to Barcelona.
- 2003-05: Users meeting and workshops to establish the scientific program. 7 beam lines approved.
- 2004: Location of CELLS at theUAB
- 2004-05: Redesign of the machine, Staff recruiting (13 different nationalities)
- 2005-08: Building.
- 27th July 2006: ground breaking
- 2008-10: Mechanical installation.
- 2008: Linac installation and commissioning
- Eastern 2009 : Movement from UAB to the new Building
- 2009-10: Booster commissioning
- 22nd March 2010: Official Inauguration
- 2011: SR commissioning



The ALBA - Building

Accelerator Division



Dieter Einfeld, CELLS-ALBA







IMMW17-2011: Project ALBA

Contents 1.) General Information 2.) Linac 3.) Booster Synchrotron 4.) Storage Ring

Dieter Einfeld, CELLS-ALBA

in St

IMMW17-2011, 21th September 2011

Accelerator

Division



Installation of Linac:
 First beam out of the Linac:
 Phase 1 Commissioning of Linac:
 Acceptance of Linac:
 Acceptance of Linac:
 Phase 2 Commissioning of Linac:
 Operation of Linac for booster commissioning:
 Reparation of Linac structure 1:
 Restart of Linac:
 Optimisation of Linac:
 Normal operation of Linac:

Febr. 2008 to May 2008 July 2008 October 2008 October 2009 Dec. 2009 to Jan. 2010 April 2010 May 2010 June – July 2010 since July 2010



Linac - Layout

Accelerator Division



Dieter Einfeld, CELLS-ALBA



LINAC in the Tunnel

Accelerator Division



Dieter Einfeld, CELLS-ALBA





All parameters are within specifications

Twiss Parameters in x and y directions:



Dieter Einfeld, CELLS-ALBA



Accelerator Division



Summary: Some specifications of the Linac are much better as given by the specifications (for example the emittance is by a factor 1.5 smaller). The Linac operation is very reliable for the different modes: long bunch, small bunch, single bunch, large charge (4 nC), small charge (0.5 nC), etc.

Dieter Einfeld, CELLS-ALBA



IMMW17-2011: Project ALBA

Contents
1.) General Information
2.) Linac
3.) Booster Synchrotron
4.) Storage Ring

Dieter Einfeld, CELLS-ALBA

1

IMMW17-2011, 21th September 2011

Accelerator

Division



Booster synchrotron

Milestones for the Installation, Commissioning, and Operation of the Booster Synchrotron

- **1.) Mechanical installation of booster:**
- 2.) Installation of RF-System :
- **3.) Installation of secondary piping:**
- 4.) Cooling available:
- 5.) Personal safety system finished:
- 6.) Alignment of booster synchrotron :
- 7.) Control system finished:
- 8.) Pre-commissioning of booster components:
- 9.) CSN- certificate for booster commissioning:
- 10.) First beam in the booster synchrotron :
- **11.)** Phase 1 of booster commissioning:
- 12.) Phase 2 of booster commissioning:
- **13.) Phase 3 of booster commissioning:**
- 14.) Reaching 3 GeV:
- 14.) Extraction of 3 GeV beam out of booster:
- **15.) Normal operation of booster synchrotron:**

Jan. 2009 to March 2009 Febr. 2009 July to Sept. 2009 September 2009 November 2009 Nov. to Dec. 2009 December 2009 Nov. to Dec.2009 December 2009 21st December 2009 10th to 24th Jan. 2010 **July 2010** Sept.- Octob. 2010 4th October 2010 28th October 2010 since Nov. 2010

Summary: The booster synchrotron runs reliable. The behaviour of the booster is pretty well understood. It is ready, working as an injector for the storage ring, but we have to make some optimisation.

Dieter Einfeld, CELLS-ALBA



Dieter Einfeld, CELLS-ALBA

Lattice of Booster Synchrotron

Accelerator Division



Dieter Einfeld, CELLS-ALBA

Som bestern Lissie Facility



Dieter Einfeld, CELLS-ALBA





Disprsion Functions (DC)

Accelerator Division



Dieter Einfeld, CELLS-ALBA



 β -function (Tune = 12.271 / 7.356) 15 β_{χ} [meters] 10 5 Ο 100 50 150 200 \mathbf{O} 15 β_y [meters] 10 5 Ο о́ 50 100 150 200 Position [meters] Good agreement with the model

GDBetae Genfeld, CELLS-ALBA

Results of the ALBA Booster commissioning IMMW17-2011, 21th September 2021

Accelerator

Division



Ramping: Tunes

Accelerator Division



- First beam to 3 GeV: injection on w.p. (12.42, 7.38)
- Large drop of Qx at the start due to nonlinear magnet calibration
- Vertical tune is flat: most of the vertical focusing is provided by the gradient bending



Ramping: Closed Orbit

Accelerator Division

Correcting the orbit while ramping



orbit corrected to ± 3 mm along the ramp

Dieter Einfeld, CELLS-ALBA



Chromaticity and Sextupoles

Accelerator Division

Chromaticity was measured during ramp by varying the RF Integrated sextupole component in combined bendings corrects natural chromaticity The two additional sextupole families to control the eddy current effects no needed so far



the measurements agree very well with the model at energy higher than 1 GeV while at low energy chromaticity is hard to be measured (still investigating)

GDBetae Einfeld, CELLS-ALBA





Dieter Einfeld, CELLS-ALBA



Booster Emittance

Accelerator Division

1st extracted Beam from the Booster Synchrotron, 28th of October 2010

File View Tau Tools Help



σ(x) = 0.86 mm, σ(y) = 0.19 mm ε(x) = 13 nmrad, ε(y) = 2,6 nmrad

We are 30 % off to the theoretical emittance and have a coupling factor of roughly 20%.

Dieter Einfeld, CELLS-ALBA



IMMW17-2011: Project ALBA

Contents
1.) General Information
2.) Linac
3.) Booster Synchrotron
4.) Storage Ring

Dieter Einfeld, CELLS-ALBA

1

IMMW17-2011, 21th September 2011

Accelerator

Division



Storage Ring Milestones

1.) Mechanical installation of storage ring:	Δ
2) Storage ring under vacuum	N
2) SAT of newer supplies :	
3.) SAT of power supplies :	0
3.) Radio frequency installation:	D
4.) Installation of injection straight:	N
5.) Cabling of magnets and power supplies:	C
6.) Cabling of signals, EPS, and MPS :	J
7.) Magnetic measurements of W80 and EPU's	J
8.) SAT of superconducting wiggler	C
9.) BTS installation finished:	S
10.) Pre-commissioning of subsystems:	
11.) Ready for storage ring commissioning:	2
12.) Installation of 3 insertion devices:	J
13.) Weekend for storage ring commissioning:	1
14.) License for storage ring commissioning:	8
15.) Bake out of in-vacuum undulators:	Ν
16.) Phase 1 of storage ring commissioning:	8
17.) Phase 2 of storage ring commissioning:	1
18.) Phase 3 of storage ring commissioning:	
19.) Installation of in-vacuum undulators and SCW	-
20) Restart of the machine:	

pril to Nov. 2009 ovember 2009 Oct. 2009 to June 2010 Dec. 2009 to April 2010 May to June 2010 Dec. 2009 to March 2010 lan. to Sept. 2010 an. to Sept. 2010 October 2010 September 2010 July to Octob. 2010 22nd of Nov. 2010 lan. to Febr, 2011 2th / 13th Febr. 2011 8th of March 2010 March to May 2011 3th to 26th of March st of April to 14th of May 25th of May to 10th of June 10th of June to 22nd of August 29th of September

Storage Ring Lattice

Accelerator Division



Dieter Einfeld, CELLS-ALBA

13/





Girder of Matching Cell



Dieter Einfeld, CELLS-ALBA



Girder of Unit Cell



Dieter Einfeld, CELLS-ALBA



Bending Magnets

Accelerator Division

25

Magnetic field:	1.42 T
Bending angle:	11.25 deg.
Gradient:	5.6 T/m
Bending radius:	7.047 m
Gap:	36 mm
Current:	520 A
Field accuracy:	<3*10 ⁻³
Grad. accuracy:	<5*10 ⁻³

The dipole is split in the middle of the magnet for machining of both pole faces with an accuracy of \pm -15 μ m.





Dieter Einfeld, CELLS-ALBA



ALBA-Lattice with nominal Settings

Accelerator Division



Dieter Einfeld, CELLS-ALBA



Bending Magnets



Dieter Einfeld, CELLS-ALBA





Rho = 6.99718, I = 1.373893 m, k = 0.568103, phi = 5.9395,

Dieter Einfeld, CELLS-ALBA
ALBA-Lattice with individual Settings

Accelerator Division



Rho = 6.99718, I = 1.373893 m, k = individual, phi = 5.9395,

Dieter Einfeld, CELLS-ALBA

Symphoton Light Facility



Accelerator Division



Dieter Einfeld, CELLS-ALBA

Symbrotron Light Facility



ALBA-Lattice with individual Settings

Accelerator Division



Dieter Einfeld, CELLS-ALBA



Specifications of SR - Quadrupole

Accelerator Division

Quadrupole magnets:

Field at pole tip:	0.715 T
Gradient:	23.43 T/m
Aperture:	61 mm
Current:	190 A
Field accuracy:	<3*10 ⁻³
Grad. accuracy:	<2*10 ⁻³
Length (mm):	200, 260
	310, 530





Dieter Einfeld, CELLS-ALBA



Pole Profile of SR - Quadrupole



Dieter Einfeld, CELLS-ALBA



Specifications of SR - Sextupole

Accelerator Division

Sextupole Magnets

Field at pole tip:	0.450 T
Diff. Gradient:	700 T/m ²
Aperture:	72 mm
Current:	200 A
Field accuracy:	<3*10 ⁻³
Grad. accuracy:	<2*10 ⁻³
Length (mm):	150, 220





Dieter Einfeld, CELLS-ALBA



Pole Profile of SR - Sextupole





D. Einfeld, CELLS



Vacuum System Layout

Accelerator Division



Dieter Einfeld, CELLS-ALBA



RF - System

Accelerator Division









Dieter Einfeld, CELLS-ALBA

IMMW17-2011, 21th September 2011



RF-System

Accelerator Division



Dieter Einfeld, CELLS-ALBA





Accelerator Division

DIAGNOSTIC SYSTEM



Dieter Einfeld, CELLS-ALBA

CIDEM - Meeting



1. Di Components

Accelerator Division

AT DIAGNOSTICS SECTION:



AT INJECTION STRAIGHT:



ALL AROUND THE RING:



DI FRONT ENDS:



Dieter Einfeld, CELLS-ALBA





The commissioning of the ALBA storage ring started at Monday the 8th of March in the afternoon with the following steps:

- **1.) Optimization of the booster and injection to SR 8th of March**
- 2.) The first turn was reached in the evening of the 9th of March with on axis injection (adjustment of energy)
- 3.) 10th of March: 20 turns with off axis injection
- 4.) 13th of March: 1 sec stored beam.
- 5.) 16th of March: first accumulated beam in ALBA (20 mA)
- 6.) 1st of April: stored beam of 100 mA
- 7.) 7th of June: stored beam 170 mA
- 8.) At the beginning of June the 1st phase of commissioning has been finished. (Reminder: The specifications of ALBA are to deliver a beam of 250 mA to the user)
- 9.) June to August: installation of SCW and 2 IVU's.
- **10.) 12th of September: restarting the machine again**
- 11.) 19th to 30th September: optimization of components
- **12.)** 3rd of October: start of 2nd phase of commissioning

Dieter Einfeld, CELLS-ALBA



Dieter Einfeld, CELLS-ALBA





Dieter Einfeld, CELLS-ALBA



Accelerator Division





Dieter Einfeld, CELLS-ALBA



1st Accumulated Beam at ALBA

Accelerator Division

16th of March 2011: a historical day of the ALBA – project: the first accumulated beam at ALBA.



Dieter Einfeld, CELLS-ALBA



1st Accumulated Beam at ALBA

Accelerator Division



A historical day of the ALBA – project, The Accelerator Division is celebrating this success.

Dieter Einfeld, CELLS-ALBA



LOCO-Measurements

Accelerator Division



Measurements 17th March





Beta-Functions of the SR

Accelerator Division

First measurements of beta function with LOCO: there is a asymmetry in the machine





LOCO - Measurements



Measurements of June



After re-cabling and applying LOCO correction



Dieter Einfeld, CELLS-ALBA



Beta-Functions of the SR

Accelerator Division





Result: It looks much better, but there is still an asymmetry in the machine (vertical)

Dieter Einfeld, CELLS-ALBA





Accelerator Division

Once the MPS was operational...

ALBA MACHINE STATUS «@comi	odus> 🥘		
CURRE	NT	100.299	mA
Life Tir	ne	0h 06m	Curr*LifeT 11.5
Filling Mode	56	Avg. Pressure (mbar)	7.34e-09
Friday 01-Apr-2011 18:25:28			
CURRENT			
	59 J119	1 ³⁹ 1 ⁵⁹	\$ ⁰
SR commissioning. Max current 90.0			



Dieter Einfeld, CELLS-ALBA



Measurements

≻ Tune

- Chromaticity
- Beam Based Alignment
- > Orbit correction, including frequency adjustment
- LOCO measurements:

Beta functions, dispersion and beating correction

- ➢ Beam size
- Bunch length
- Vacuum performance
- Closing IDs
- Slow orbit correction system
- > Others

(Most of these measurements were done with <u>10~20 mA</u>)



Accelerator Division



Dieter Einfeld, CELLS-ALBA

13/

Symbrotron Light Facility



Beam Based Alignment

BBA : Results



IMMW17-2011, 21th September 2011

Accelerator

Division





Dieter Einfeld, CELLS-ALBA



Orbit Correction, evolution



Dieter Einfeld, CELLS-ALBA



Orbit Correction

Accelerator Division

Raw orbit without correctors

Offsets of BBA included and RF frecuency adjusted



Storage Ring Orbit (Difference from the Offset Orbit)

Dieter Einfeld, CELLS-ALBA



Orbit Correction: Reproducibility

Raw orbit with correctors Orbit)

Accelerator

Division





Tune during the commissioning:

Accelerator Division



Normally working with chromaticity: +2, +2

Dieter Einfeld, CELLS-ALBA



• 7 or 8 BPM/cell (120 BPMs): orbit control and interlock system

• Low-loss phase matched (<10deg) RF cables of wide variety of lengths [15m - 45m]



Dieter Einfeld, CELLS-ALBA



Final LOCO - Measurements

Accelerator Division



Horizontal Dispersion: The deviations to the model are +/- 5 mm. Good agreement.

Vertical Dispersion: +/- 15 mm the vertical dispersion is given by the cross talk of the BPM's. With the introduction to LOCO, it could be decreased to 1 mm

Dieter Einfeld, CELLS-ALBA



LOCO - Results



Dieter Einfeld, CELLS-ALBA

IMMW17-2011, 21th September 2011

Accelerator

Division


Injection Efficiency



Dieter Einfeld, CELLS-ALBA



Beam Size

Accelerator Division

And...



Dieter Einfeld, CELLS-ALBA

Apple II EU62 , EU71 and MPW are installed





Dieter Einfeld, CELLS-ALBA



Streak Camera

Accelerator Division

Visible Radiation from a dipole is extracted using a mirror
Mirror position (in-vacuum) controlled with thermocouples

Example: Bunch Length Measurement



Bunch length vs. RF voltage



Dieter Einfeld, CELLS-ALBA



Dieter Einfeld, CELLS-ALBA

7th of June: 170 mA at ALBA

Accelerator Division



Dieter Einfeld, CELLS-ALBA

13/

Symbrotron Light Facility



0

Vacuum System Commissioning

Accelerator Division

- Average pressure without beam = <u>4·10⁻¹⁰ mbar.</u>
- With 4.5 A.h. dose, the average pressure was <u>3.2.10⁻⁹ mbar</u> with 80 mA of beam current (multi-bunch filling mode).
- Vacuum Clean-up rate estimated 0.68.





Photon-stimulated desorption yield (PSD) vs. beam dose.



Average pressure normalized to current vs. beam dose

IMMW17-2011, 21th September 2011

Dieter Einfeld, CELLS-ALBA



Front End Layout

Accelerator Division



Dieter Einfeld, CELLS-ALBA



Summary of Measurements



(Most of these measurements were done with 10~20 mA)



Problems and Next Steps

- RF problems LLRF deregulation, water leaks, vacuum leaks, trips ...
- Vacuum problems Water configuration, chamber overheating, leaks …
- Diagnostics problems Streak camera, Libera electronics, stack FS …
- PS problems Wrong cabling, correctors and quadrupoles PS ...
- Control system problems Applications froze, motors, CCD camera, cycling, MPS, PSS, timing …

Next Steps

- Commissioning with ID's
- Slow orbit feedback
- Vacuum cleaning
- Better control filling pattern
- Fast orbit feedback
- Multibunch feedback
- Topping up

Dieter Einfeld, CELLS-ALBA



SCW and IVU's are installed

Accelerator Division



Dieter Einfeld, CELLS-ALBA



Thank you very much

Accelerator Division



This was not only a success from the commissioning team, it was a success of the whole CELLS staff





The machine is ready to serve as a source

for the experiments







Dieter Einfeld, CELLS-ALBA



Layout of LTB Transfer Line





Dieter Einfeld, CELLS-ALBA

IMMW17-2011, 21th September 2011

Accelerator

Division

Layout of BTS Transfer Line

Accelerator Division



Dieter Einfeld, CELLS-ALBA

ALBA



RF-System

Accelerator Division



Dieter Einfeld, CELLS-ALBA